City of Wichita, Kansas Americans with Disabilities Act Transition Plan

Delano Park

101 North Mclean

July 2005



Prepared by

DMCG

Disability Management Consulting Group L.L.C.

2801 Jonquil Place Columbia, MO 65202

In conjunction with

The Great Plains ADA & IT Center and the City of Wichita Disability Advisory Board

City of Wichita - ADA/504 Transition Plan - Delano Park - July 2005 Legend: Blue font identifies hyperlinked documents - Red font indicates recommended changes to structures or policies

Locations	Structural Inconsistencies		Recommended Corrections/Modifications to Ensure Program Access	Criteria – L=low, M=medium, H=high		\$		mental Technical nformation	Finalized Actions			
Location	Identified Issue	ADAAG Specifications	Recommended Correction	Priority (overall)	Public Access	Frequency - PWD	Photo #	Conceptual Costs	Support Information	Finalized Correction	Date to be Corrected	Date Completed (Include initial)
1. Parking	Accessible parking does not exist due to a dirt/grass/gravel surface, and steep slopes.	4.5.2	ADAAG requires all accessible routes and spaces, including access aisles at accessible parking, to be stable, firm and slip-resistant. The existing gravel/grass surface does not meet this specification. In addition, ADAAG requires accessible parking spaces and access aisles to have surface slopes that do not exceed 2%. Create accessible parking spaces, if other vehicles are allowed to park in this area, which meets ADAAG specification. Note: Only the access aisle, at accessible parking is required to meet ADAAG's surface specifications. The vehicle parking space can be a gravel surface.	L	L	M	<u>0</u> <u>1</u>	\$750	See the Accessible Parking Detail for more information on parking surfaces.			
2. Pedestrian Paths	An accessible route does not exist, leading to the seating area in front of the stage, due to dirt/grass surfaces.	4.3.2	At least one accessible route shall connect accessible buildings, facilities, elements, and spaces that are on the same site. Accessible routes are required to be stable, firm and slip-resistant. Create an accessible path (concrete, asphalt, rubber) of travel leading to the stage seating area and create at least one wheelchair seating location, which complies with 4.33.2, 4.33.3, and 4.33.4 and consistent with table 4.1.3(19)(a).	L	L	M	2	\$750	ADAAG See Building Block 15 – Assembly Areas			
3. Stage	The only path of travel to the stage level consists of steps.	4.3.2	According to ADAAG, at least one accessible route shall connect accessible buildings, facilities, elements, and spaces that are on the same site. In addition, if an accessible route has changes in level greater than 1/2 in (13 mm), then a curb ramp, ramp, elevator, or platform lift (as permitted in 4.1.3 and 4.1.6) shall be provided that complies with 4.7, 4.8, 4.10, or 4.11, respectively. An accessible route does not include stairs, steps, or escalators. Ensure that an accessible path of travel exists leading to the Stage, without steps.	L	L	M	3	\$1,50 0	ADAAG			
	Note: The stage is the only facility located within the park.											

Delano Park - Conceptual Cost Projections

Total	\$3,000
Year One (Very High)	\$0
Year Three (High)	\$0
Year Five (Medium)	\$0
Year Ten (Low)	\$3,000